

**CORRIGENDUM**

Dated: 31.03.2016

The sealed item rate Press Inviting tender were called for on dated 13.03.2016 published in the News Papers and uploaded on the College website i.e. satyawati.du.ac.in for the Repair/strengthening/ raising of brick masonry boundary wall around the College premise and trengthening/ Reconstruction of main Carriageway & Parking area at Satyawati College, Ashok Vihar, Phase-III, Delhi.  
The following correction are made in the quantity and quote the rates accordingly.

**Name of Work: Repair/strengthening/ raising of brick masonry boundary wall around the College premise**

**Schedule of Quantity for Boundary Wall**

S. No.	Description	Quantity	Unit	Rate	Amount in (₹)
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand). (The bricks shall be provided by the Department /College free of cost)	<u>200</u>	Cum		

**Name of Work: Strengthening/ Reconstruction of main Carriageway & Parking area .**

S.No.	Description	Quantity	Unit	Rate	Amount
2	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :All kinds of soil Pipes, cables etc. exceeding 300 mm dia but not exceeding 600 mm	<u>301.95</u>	Metre		
3	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :450 mm dia. R.C.C. pipe	<u>301.95</u>	Meter		

There is no change in other items with the same terms and conditions as earlier called for.



*Manjula Dass*

(Dr. Manjula Dass)  
Principal( Offg.)