

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI

Ref no. UE/ 81 / DU/ M-21 (2016-17) dated 28/6/16

Sealed percentage rate quotations are here by invited from Contractors enlisted with CPWD, MES, Railways and working Contractors of Delhi University for the work " P/F Signage ,Board , glass pan in Muisc Faculty and Fine Arts , University of Delhi, So as to reach the office of the Undersigned at 3.00 PM on dated :30.06.2016

S.No	Description of item	Qty	Unit	Rate	Amount
1	Excavating holes more than 0.10 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil, as directed within a lead of 50 m and lift upto 1.5 m. All kinds of soil	6	each	50.05	300.3
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	1	cum	5466.3	5466
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	100	kg	90.1	9010
4	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	100	kg	619.4	61940
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	1	cum	892.7	893
6	Manufacturing, supplying and fixing retro reflective sign boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle				

iron of size 25x25x3 mm along with theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up to M.S. Tee section ISMT 50x50x6 mm welded with base plate of size 100x100x5 mm at the bottom end and including making holes in pipes, angles flats, providing & fixing M.S. message plate of required size, steel work to be painted with two or more coats of synthetic enamel paint of required shade and of approved brand & manufacture over priming coat of zinc chromate yellow primer (vertical MS-Tee support to be painted in black and white colours). Backside of aluminium sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing, specification and direction of Engineer-in-charge.

16.59.1 Mandatory/ Regulatory sign boards of 900 mm diametre with support length of 3750 mm

10	sq m	4912.35	49124
----	------	---------	-------

7 Providing and fixing computerized digital printed plates on 3 mm thick foam sheet (Sun board) for room , office room , toilet, direction with necessary screws etc complete as per direction at site

20000	s.inch	2	40000
			166734

Conditions :-

1. The work is to be completed with 20 days
2. 1.50 % water charges will be deducted
3. CPWD Specifications will be followed
4. Rates should be quoted both in words & figures.
5. Undersigned reserves the authority to reject any or all the quotation without any reason therefore .
6. SC/ST Contractors shall enclosed copies of attested cast certificate other wise there quotation will be accepted.
7. Contractor shall enclosed the copy of Labour Licence Registration with ETFO , ESIC and BOCW welfare board other wise there quotation will not be accepted .

Executive Engineer

I here by quote % rate above / below / At Par on estimated cost of Rs.166734.00

Contractor

1. The Director computer center with a request to display the inviting quotation on the University of Delhi website.
2. Mrs. Kavita , JACT , for information and to ensure the display of the quotation on University website.
3. Section Officer -II
4. Notice Board

Executive Engineer