

ENGINEERING DEPARTMENT

UNIVERSITY OF DELHI

DELHI-110007

Ref. No. UE/

124

/DU/M- (2016-2017)

dated

15/7/16

NOTICE INVITING QUOTATION

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work " **Repair work PVC tank and Signage board in International Guest House, University of Delhi** " So as to reach the office of the undersigned upto 3.00 P.M. on 19/7/2016

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, ISI : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	10000	ltr	7.25	72500.00
2	Providing and fixing PTMT extension nipple for water tank pipe, fittings of approved quality and colour. 20 mm nominal bore, weighing not less than 40 gms	4	each	51.15	205.00
3	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball. 20 mm nominal bore, 120 mm long, weighing not less than 198 gms	4	each	285.60	1142.00
4	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 20 mm dia nominal bore	4	metre	249.30	997.00
5	Providing Retro-reflective regulatory sign board of size 900 mm dia meter made out of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated lens type retro-reflective sheeting as approved by Engineer-in-charge. Letter, symbols, borders etc. will be as per IRC - 67 with required colour scheme on the boards and with the high intensity grade A. The aluminium sheet to be riveted to M.S. frame of angle iron of size 40x40x4 mm. The boards will be fixed to 1 No. 50x50 mm square post made of M.S. angle 50x50x4 mm, 4 m long welded to the frame with adequate anti-theft arrangement. Sheet work to be painted with two or more coats of synthetic enamel paint over an under coat (primer) and back side of aluminium sheet to be painted with two or more coats of epoxy paint including appropriate priming coat complete in all respects as per direction of Engineer-in-charge.	3	sqm	5441.30	16324.00
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	600	Kg	90.10	54060.00
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	1	cum	5466.30	5466.00
8	P/F gun metal gate valve 20 mm dia. (DRP/ Leader)	4	each	910.00	3640.00
				Total	154334.00

Condition:

- The work should be completed in 25 days.
- 1.5% water charges will be deducted.
- Rates should be quoted both in words & figures.
- The contractor must visit the site before quoting his rates.
- CPWD specification in force will be followed.
- Contractor shall enclose copies of labour license registration with EPFO, ESIC and BOCW Welfare board otherwise their quotation will not be accepted.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

SOL
Executive Engineer

I/we hereby quote % above/below/at par on the estimated cost of Rs.154334/-

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- The Director, Computer Center with a request to display the Notice Inviting quotation on the Delhi University Website.
- Sh. Ashok Kr. Tripathi, J.E. (C)
- Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- Notice Board

QV
Executive Engineer