

ENGINEERING DEPARTMENT  
UNIVERSITY OF DELHI  
DELHI-110007

Ref. No. UE/ 130 /DU/EM-01 (2016-2017)

dated 29/7/16

NOTICE INVITING QUOTATIONS

Sealed item rate quotations are hereby invited in two bid system in two separate envelope with super scribed on the envelope one for eligibility and 2nd for price bid from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work" **Replacement of defective street light pole cable and painting of the existing street light pole and dressing the cables and hanging wires in the Delhi School of Economics Complex and FMS, University of Delhi.** ' So as to reach the office of the undersigned upto 3.00 P.M. on 03.08.2016

Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1	Laying of one number of XLPE insulated & PVC sheathed aluminum conductor armored power cable of 1.1 KV grade direct in ground i/c excavation, sand cushioning protective covering & making good the same etc. as reqd.				
a	Upto 35 Sqmm	150	Mtr		
2	Painting the existing street light pole with two or more coat i/c rubbing the corrosion and applying one or moat coat of primer as reqd.	30	Nos		
3	Installation of existing street light fitting on the existing pole i/c making connection etc. as reqd	5	Nos		
4	Dressing up the hanging wire,cables by proper shutteling,clamping as reqd i/c making good the same	1	Job		
5	Making provision for connection of existing street light pole box with TPN connector i/c proper thimbling , taping and connection as reqd.	80	Nos		
6	S/F of copper thimble suitable for 16 sqmm capacity i/c connection as reqd	320	Nos		
7	S/F street light junction box of size 8"x10"x4" deep PVC sintex box having Bakelite sheet with brass nut bolts, neutral link 1 No. 16 Amp SPMCB fixed with G.I strip clamp 2 Nos.of size 20x5 mm.etc. as reqd.	10	each		
8	S/D the following size FRLS of PVC insulated copper conductor cable in the existing surface /recess PVC conduit as reqd.				
a	1x1.5	100	mtr		
b	2x2.5	50	Mtr		
c	2x4	50	mtr		
d)	Cat-6 internet wire	100	Mtr		
9	Supplying and fixing of following sizes of PVC conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required. <b>20 mm(AKG/BEC)</b>	100	mtr		
10	S/F DLP UPVC trunking compartment with cover clip on separates partition left right top internal angle, flat angle raise function flat function cover to body joints mosaic clip & support from mosaic isolation bracket 2 mm thick plastic.				
b	80 mm x 50 mm with all accessories.	20	mtr		
11	S/F/ testing & commissioning of prewired LED single box type fitting (1x20 watts) complete with all accessories and one 20 watt tube(stellar bright ) of 2100 lumen, 6500 k etc. directly on ceiling or wall i/c connection with 1.5sqmm FR PVC copper cond. cable etc. as reqd. (TMC 501 P 1x T - LED 22W P3241) (Philips make)	5	Nos		
12	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required				
a	3 pin 5/6 amp socket outlet	20	Nos		
b	5/6 amps switch	5	Nos		
c	15/16 amp switch	10	Nos		
d	15/16 amp socket	10	Nos		
13	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required <b>Single pole</b>	15	Nos		
14	Supplying and fixing 2 Module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	8	each		
15	S/F Bakelite sheet of following sizes i/c cutting the hole for existing Switch & socket etc. as reqd.				
a	10"x12" of 3 mm thick	5	each		
b	9"x11" of 3 mm thick	4	each		
c	8"x5" of 3 mm thick	6	each		
d	5"x5" of 3 mm thick	11	each		
e	T cover.	48	each		

P.T.O



16	P/ Fixing 12" sweep heavy duty exhaust fan in the existing opening i/c testing, connectionist as reqd. at site. (900 RPM)	3	each
17	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.		
a	12 Module	2	each
b	6 Module	2	each
c	3 Module	6	each
18	Supplying /fixing following accessories in the existing street light fittings i/c connection, testing and dismantling etc. as reqd.		
a	250 Watt HPSV chocke	1	Nos
b	250 Watt HPSV lamp	2	Nos
d	igniter	3	Nos
e	160 Watt MLL lamp	5	Nos


**TOTAL**

**Specific Make**

Wire : Havells\Finolex\skytone/RR Kabel  
Switch, socket : Norht west\Legrand\ Seimens  
PVC Conduit/Batten : AKG/BEC/polycab  
DLP Trunking : Legrand  
Pole Box : Syntex

**Condition:-**

- 1 The work should be completed in 20 days
- 2 Rates should be quoted both in words & figures.
- 3 CPWD specification in force will be followed.
- 4 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.
- 5 Contractor shall enclose copies of EPFO, ESIC ,Labour registration along with their quotation , otherwise their quotation will not be accepted.

  
Executive Engineer


**Undertaking:**

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

**Copy to:-**

- 1 The Director, Computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- 2 Sh. S.B. Tyagi, A.E. (E)
- 3 Sh. Devendra Kumar, J.E(E)
- 4 Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 5 Notice Board

  
Executive Engineer