

**ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007**

NOTICE INVITING QUOTATIONS

Ref. No. UE/ 156

/DU/EM (2016-2017)

Dated

16/8/16

Sealed item rate quotation are here by invited two envelop system one for eligibility and second for financial for the contractors enlisted with, C.P.W.D , MES, Railways & working contractors of Delhi University for" Provision of power points and minor electric work to be carried out in Pathology lab W.U.S Health Center, Shivaji Collage , University of Delhi. 'So as to the reach the office of the undersigned upto 3.00 P.M. on..... 22/8/16

S. No	Description of Items	Qty	Unit	Rate	Amount
1	S/F DLP UPVC trunking compartment with cover clip on separates partition left right top internal angle, flat angle, raise function, flat function cover to body joints mosaic clip & support from mosaic isolation bracket 2 mm thick plastic. (Legrand) 105 mm x 50 mm with all accessories.	15	mtr		
2	wiring for light point/fan point/exhaust fan point/cell bell point with 1.5 sqmm FRLS PVC insulated copper conductor , single core cable in the existing surface/ recessed PVC conduit with modular type, switch suitable size G.I box and earthing the point with 1.5 sqmm FR PVC insulated copper cond. Single core cable etc as reqd. Group B	6	nos		
3	Supplying and fixing of following sizes of medium class PVC conduit/Batten along with all accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.				
a	20mm	15	mtr		
4	S/D the following size FRLS of PVC insulated copper conductor cable in the existing surface /recess PVC conduit as reqd.				
a	1 x 1.5 sqmm	15	mtr		
b	2 x 2.5 sqmm	15	mtr		
c	3 x 4 sqmm	100	mtr		
d	3 x 10 sqmm	15	mtr		
5	S/F Tiny Trip AC box complete with all accessories with plug and top on surface/recessed and making the good the same etc asreqd. At site and 1 nos 25 amp g series SP MCB connection etc as reqd. at site	4	nos		
6	S/F 6 module power box with screw lass decorative plate modular having 2 nos Switch 15/16 amp and 2 nos socket 6 pin 15/16 making connection etc as reqd.	8	nos		
7	S/F/ testing & commissioning of prewired fluorescent fitting double box type fitting (2x36watts) complete with all accessories and p/f 2 nos 36W tube etc. on the exisitng down rod i/c connection with 1.5sqmm FR PVC copper cond. cable etc. as reqd. (TMC 501 2xTLD 36W EBE) (Philips make)	7	Nos		
8	Supplying and fixing following way prewired SP&N MCB distribution board of steel sheet for 240 volts on surface/ recess complete with loose wire box, terminal connectors for all incoming and outgoing circuits, duly prewired with suitable size FR PVC insulated copper conductor up to terminal blocks, tinned copper bus bar, neutral link, earth bar, din bar, detachable gland plate, interconnections, powder painted including earthing etc. as required. (But without MCB/ RCCB/ Isolator)				
a	2 + 12 way, Double door	1	Nos		
9	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	10	nos		
10	Supplying and fixing following 63 amp, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.	1	Nos		
11	S/I/T/C of 12" Heavy Duty Exhaust fan with suitable size louver shutter I/C wooden work if read.	1	nos		
12	S/F LED street lights 25 W fitting luminaire with pressure dia cast aluminium and heat resistance toughened flat glass complete with accessories i/c making connections etc reqd	1	Nos		
13	S/F Wall Fan complete with all accessories i/c connection and testing the same etc.as reqd.(Orient/Crompton)	2	nos		
14	S/F G.I bracket 1.20 mtr i/c welding with 2 nos. clamps etc as reqd.	1	nos		

- 15 Supplying and fixing 3 x 4 sqmm of one number PVC insulated and PVC sheathed /XLPE 20 mtr
power cable of 1.1 KV grade of following size direct in ground including excavation, sand
cushioning , protective covering ,refilling the trench etc as reqd.

Total

Spcific make:

- | | | | |
|---|------------------|---|-----------------------------------|
| 1 | Wire/cable | : | Finolex/Skytone/RR kabel/Grandlay |
| 2 | Switch/socket | : | North-west/Cona |
| 3 | DLP trunking | : | Legrand/Hagger |
| 4 | SP MCCB/Isolator | : | Legrand/Hagger |

Condition:

- 1 The work should be completed in 4 days.
- 2 Rates should be quoted both in words & figures.
- 3 CPWD specifications will be followed.
- 4 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therofre
- 5 Contractor shall enclose copis of labour registration , ESIC, EPFO along with their bid otherwise their quotation will not be accepted

Executive Engineer

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.□

(Contractor)

Copy to:

- 1 The director, Computer Center with a request to display the notice inviting quotation on the Delhi University Website.
- 2 Sh.S.M Goel J.E (E)
- 3 Mrs. Kavita JACT to ensure the display of the quotation notice on University website.
- 4 Notice Board



Executive Engineer