

ENGINEERING DEPARTMENT

UNIVERSITY OF DELHI

Delhi 110007

NOTICE INVITING QUOTATION

Ref. No. UE/ 568 /DU/M- (2018-2019)

dated 1/10/18

Sealed percentage rate quotation are hereby invited from the contractors enlisted with CPWD., MES, Railways and any Govt./public sector undertaking and working contractor of Delhi University for the work "Repair of Grill and Finishing work in front of Central Science Library, University of Delhi." So as to reach the office of the undersigned up to 3.00 PM on 10/10/18

S.No.	Description of Items	Unit	Qty	Rate	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	70	9.9	693.00
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	cum	5	123.7	618.50
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :With cement mortar 1:4 (1cement: 4 coarse sand)	sqm	3	259.15	777.45
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	50	74.4	3720.00
5	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10	sqm	70	90	6300.00
6	Providing and applying birla / JK wall putty on wall surface (one or more coats) as required in thickness upto 1 mm i/c sand papering etc to prepare smooth as per direction of Engineer-in-charge.	sqm	20	67.85	1357.00
7	Repair & refixing of MS grill/ railing after making functional i/c cutting, welding etc complete as per direction of Engineer-in-charge.	job	1	1381	1381.00
				Total	14846.95

Condition:-

- The work should be completed in 07 days.
- 1.50 % water/Electric charges will be deducted.
- Rates should be quoted both in words & figures.
- The contractor must visit the site before quoting his rate.
- CPWD specification in force will be followed.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore

I/we hereby quote.....% above/ below/ at par on the estimated cost of Rs.14846.95

Undertaking

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Executive Engineer

- The Director, computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- Sh. Ajay Malik, J.E. (C)
- Ms.Kavita, J.A.C.T. to ensure the display of the tender notice on University website
- Notice Board.

Executive Engineer