

**ENGINEERING DEPARTMENT  
UNIVERSITY OF DELHI  
Delhi 110007  
NOTICE INVITING QUOTATION**

Ref. No. UE/ <sup>592</sup> ~~592~~ /DU/M-54 (2018-2019)

dated

Sealed percentage rate quotation are hereby invited from the contractors enlisted with CPWD., MES, Railways and any Govt./public sector undertaking and working contractor of Delhi University for the work "Repair work tiles, plaster, wire mesh jali and painting in mesh at Social Work Hostel, University of Delhi." So as to reach the office of the undersigned up to 3.00 PM on 11/10/18

1	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete. With 12 mm mild steel U beading	sqm	2	578.3	1156.60
2	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting,	sqm	1	836.65	836.65
3	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty; Float glass panes of thickness 4 mm	sqm	1	690.7	690.70
4	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	100	9.9	990.00
5	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	sqm	100	67.3	6730.00
6	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 15 mm dia nominal bore	metre	5	215.1	1075.50
7	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	each	1	367.75	367.75
8	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 15 mm nominal bore	each	1	165.25	165.25
9	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	each	2	610.66	1221.32
10	P/F fibre sheet (2 mm thick) roofing with wall putty coated J or L hooks, nats and bolts etc complete. As per direction of Engineer in-charge.	sqm	1.5	1125.24	1687.86
				<b>Total</b>	<b>14921.63</b>

Condition:-

1. The work should be completed in 07 days.
2. 1.50 % water/Electric charges will be deducted.
3. Rates should be quoted both in words & figures.
4. The contractor must visit the site before quoting the rates.
5. CPWD specification in force will be followed.
6. Undersigned reserves the authority to reject any or all the quotation without assigning.

*SN*  
Executive Engineer

I/we hereby quote.....% above/ below/ at par on the estimated cost of Rs. 14921.63

we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

1. The Director, Computer Center with a request to display the Notice Inviting quotation on the Delhi University Website.
2. Sh. Ashok Tirpathi, J.E.(C)
3. Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
4. Notice Board

*[Signature]*  
Executive Engineer