

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007
NOTICE INVITING QUOTATIONS
(2018-2019)

Ref. No. UE/

628

/DU/M-

dated

8/10/18

Sealed percentage rate quotations are hereby invited from the contractors enlisted with CPWD, MES, Railways and any Govt./ public sector undertaking and working contractor of Delhi University for the work "Misc. repair of work finishing work, repair of plaster due to seepage etc in Hindi Medium, University of Delhi." So as to reach the office of the undersigned upto 3.00 P.M. on 16/10/18

S. No Description of Items

| S. No | Description of Items | Unit | Qty | Rate | Amount |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----|--------------|-----------------|
| 1 | Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work | sqm | 100 | 50.65 | 5065.00 |
| 2 | Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer | sqm | 100 | 35.85 | 3585.00 |
| 2 | Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead With cement mortar 1:4 (1 cement : 4 fine sand) | sqm | 5 | 247.8 | 1239.00 |
| 3 | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. | sqm | 100 | 9.9 | 990.00 |
| 4 | Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. | cum | 5 | 123.7 | 618.50 |
| 5 | Providing and applying birla / JK wall putty on wall surface (one or more coats) as required in thickness upto 1 mm i/c sand papering etc to prepare smooth as per direction of Engineer-in-charge. | sqm | 50 | 67.85 | 3392.50 |
| | | | | Total | 14890.00 |

Condition:

- 1 The work should be completed in 07 days.
- 2 1.50 % water/ electric charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.14890.00
Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

Sd
Executive Engineer

Contractor

- 1 The Director, Computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- 2 Ms. Kavita, J.A.C.T. to ensure the display of the tender notice on University website
- 3 Notice Board.

4. Astor Titalkh S (CC)

Sd
Executive Engineer