

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007

Ref. No. UE/

705

/DU/M- (2018-2019)

dated

29/10/18

NOTICE INVITING QUOTATION

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work, "Providing and fixing push cock for the Urinals in the toilets of Old USIC Building, University of Delhi." So as to reach the office of the undersigned upto 3.00 P.M. on 29/10/2018

Sl. No.	Item	Qty	Unit	Rate	Amount
1	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	4	sqm	836.35	3347.00
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	4	sqm	28.20	113.00
3	Providing and fixing PTMT 15 mm Urinal spreader size 95x69x100 mm with 1/2" BSP thread and shapes, weighing not less than 60 gms.	12	Nos.	188.20	2258.00
4	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour. 15 mm nominal bore with 30cm length	10	each	62.45	625.00
5	Providing and fixing PTMT push cock (Prayag or equivalent make) i/c taking out of existing damaged sensor kits and fixing the push cocks with all necessary fittings like Tee, Elbow etc. complete as per direction of Engineer-in Charge.	10	Nos.	565.00	5650.00
6	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved	12	cum	123.70	1484.00
				Total	13477.00
				Say	13477.00

Condition:

- 1 The work should be completed in 07 days.
- 2 1.5% water charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 The contractor must visit the site before quoting his rates.
- 5 CPWD specification in force will be followed.
- 6 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.13477/-

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- 1 The Director, Computer Center with a request to display the Notice Inviting quotation on the Delhi University Website.
- 2 Sh. Ajay Malik, J.E. (C)
- 3 Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 4 Notice Board

Executive Engineer