

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007

NOTICE INVITING QUOTATIONS

Ref. No. UE/

158

/DU/M-54 (2014-2015) dated

18/9/14

Scaled item rate quotations are hereby invited from the contractors enlisted with CPWD, MES, Railways and any Govt./ public sector undertaking and working contractor of Delhi University for the work "BRC jali fencing for D-5 and D-6 (29-31) Probyn Road, University of Delhi.." So as to reach the office of the undersigned upto 3.00 P.M. on

25-9-14

S. No	Description of Items	Unit	Qty	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	cum	8		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	cum	1		
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., up to floor five level, excluding the cost of centering, shuttering and finishing 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	0.5		
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	6		
5	Providing and fixing hard drawn steel wire fabric 75x25 mm mesh of weight not less than 7.75 Kg per sqm to window frames etc. including 62x19 mm beading of second class teak wood and priming coat with approved steel primer all complete.	sqm	40		
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg	380		
7	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	sqm	30		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	40		
9	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	cum	8		

Total Rs.

Condition:

- 1 The work should be completed in 07 days.
- 2 1.50 % water / electric charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

Contractor

- 1 The Director, Computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- 2 Sh. Jacob John, J.E. (C)
- 3 Ms. Kavita, J.A.C.T. to ensure the display of the tender notice on University website
- 4 Notice Board.

Executive Engineer

Executive Engineer