

ENGINEERING DEPARTMENT

UNIVERSITY OF DELHI

DELHI-110007

Ref. No. UE/ 97

/DU/M- 01 (2015-2016)

dated

19/6/15


NOTICE INVITING QUOTATIONS

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Face lifting the Auditorium and Law Faculty main building, University of Delhi. So as to reach the office of the undersigned upto 3.00 P.M. on.....23.6.15

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	30	sqm	215.40	6462.00
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	300	sqm	41.35	12405.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	500	sqm	9.00	4500.00
4	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm (nothing extra will be paid for height)	10	sqm	651.40	6514.00
5	Finishing walls with Premium Acrylic Smooth exterior paint withSilicone additives of required shade				
a)	Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface	500	sqm	69.45	34725.00
b)	Old work (one or more coats applied @ 0.83 ltr/10 sqm).	2000	sqm	45.55	91100.00
6	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	180	sqm	18.15	3267.00
7	Rough cast plaster upto 10 m height above ground level with a mixture of sand and gravel or crushed stone from 6 mm to 10 mm nominal size, dashed over and including the fresh plaster in two layers, under layer 12 mm cement plaster 1:4 (1 cement : 4 coarse sand) and top layer 10 mm cement plaster 1:3 (1 cement : 3 fine sand) mixed with 10% finely ground hydrated lime by volume of cement. Ordinary cement finish using ordinary cement	150	sqm	371.25	55688.00
8	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	3	cum	123.85	372.00
				Total	215033.00

Condition:

- The work should be completed in 45 days.
- 1.5% water charges will be deducted.
- Rates should be quoted both in words & figures.
- The contractor must visit the site before quoting his rates.
- CPWD specification in force will be followed.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.


 Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.215033/-


Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- The Director, Computer Center with a request to display the Notice Inviting quotation the Delhi University Website.
- Sh. Vinod Kr. Jain, A.E. (C)
- ✓ Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- Notice Board


 Executive Engineer

Agency

Address

Contract No.