

**ENGINEERING DEPARTMENT  
UNIVERSITY OF DELHI  
DELHI-110007**

Ref. No. UE/ 160 /DU/M- (2015-2016) dated 19/6/15

**NOTICE INVITING QUOTATIONS**

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Repair of one No. bore well and making refunfunctional another bore well at Mughal Garden, University of Delhi So as to reach the office of the undersigned upto 3.00 P.M. on 25/6/15

Sr. No.	Description of items	Qty	Unit	Rate	Amount
1	Excavating holes upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil; as directed within a lead of 50 m and lift upto 1.5 m. All kinds of soil.	4	Nos.	47.15	189.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.5	cum	4921.70	2461.00
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	10	sqm	63.05	631.00
4	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work - Exposed on wall 32 mm dia. nominal bore	18	sqm	333.50	6003.00
5	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	1	Nos.	338.90	339.00
6	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 20 mm nominal bore.	2	Nos.	407.40	815.00
7	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	100	kg	86.50	8650.00
8	Boring with 150 mm dia casing pipe tube well in also soil except ordinary hard rock reqd. blasting as Direct of Engineer in Charge.	42	mtr	677.00	28434.00
9	Casing pipe 150 mm dia . Class ISI marked with necessary clamp	42	mtr	1183.00	49686.00
10	P/F commissioning of 1 HPO vertical type submersible pump (Crompton)	1	Nos.	16422.00	16422.00
11	P/F panel for submersible pump (Crompton) CPB 1.0	2	Nos.	3379.00	6758.00
12	Priming of bore well upto clean water	2	Job	1455.00	2910.00
13	P/F steel wire with PVC coated suitable for hanging submersible pump.	40	mtr	24.00	960.00
14	P/Welding 150 mm dia M.S. socket	14	Nos.	449.00	6286.00
15	Making slotter in 150 mm casing pipe.	12	mtr	230.00	2760.00
16	Taking out and relowering of 1 HP vertical type submersible pump in the bore well.	1	Job	1500.00	1500.00
				<b>Total</b>	<b>134804.00</b>

**Condition:**

- The work should be completed in 10 days.
- 1.5% water charges will be deducted.
- Rates should be quoted both in words & figures.
- The contractor must visit the site before quoting his rates.
- CPWD specification in force will be followed.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

  
Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of **Rs.134804/-**


Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- The Director, Computer Center with a request to display the Notice Inviting quotation the Delhi University Website.
- Sh. Ashok Kr. Tripathi, J.E. (C)
- Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- Notice Board

  
Executive Engineer