

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007

Ref. No. UE/

180

/DU/M- 01 (2015-2016)

dated

12/8/15


NOTICE INVITING QUOTATIONS

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Distemping painting the toilets verandah of main building Law Faculty, University of Delhi. So as to reach the office of the undersigned upto 3.00 P.M. on.....17-8-15

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	200	sqm	45.25	9050.00
2	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	15	sqm	215.40	3231.00
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	500	sqm	41.35	20675.00
4	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	500	sqm	9.00	4500.00
5	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1 cement : 4 fine sand)	20	sqm	221.15	4423.00
6	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm	10	sqm	651.40	6514.00
7	Distemping with 1st quality acrylic washable distemper (ready made) of approved manufacturer and of required shade and colour complete. as per manufacturer's specification. One or more coats on old work	3800	sqm	25.70	97660.00
8	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	15	sqm	18.15	272.00
9	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1	cum	123.85	124.00
10	Providing and applying birla / JK wall putty on wall surface (one or more coats) as required in thickness 1 mm i/c sand papering etc to prepare smooth as per direction of Engineer-in-charge.	250	sqm	57.00	14250.00
11	Repair of door i/c taking out, repair, refixing and locking arrangement etc complete	20	each	336.00	6720.00
				Total	167419.00

Condition:

- The work should be completed in 45 days.
- 1.5% water charges will be deducted.
- Rates should be quoted both in words & figures.
- The contractor must visit the site before quoting his rates.
- CPWD specification in force will be followed.
- Contractor has to make the arrangement for taking out office/class room furniture for execution of work and re-setting the same after execution of work if required.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.


Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.167419/-


Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- The Director, Computer Center with a request to display the Notice Inviting quotation the Delhi University Website.
- Sh. Vinod Kr. Jain, A.E. (C)
- Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- Notice Board


Executive Engineer

Agency

Address

Contract No.