

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI

Ref no. UE/ 183 / DU/ M- 21 (2015-16)

dated

13/8/15

Sealed item rate short notice quotations are here by invited from Contractors enlisted with CPWD, MES, Railways and working Contractors of Delhi University for the work " Repairs the damaged chajja and change room floor, auditorium chair, pvc floors and toilet fittings at Sir Shanker Lal Hall, University of Delhi, So as to reach the undersigned at 3.00 PM on dated : 14.8.15"

S.No	Description of item	Qty	Unit	Rate	Amount
	Specific brands to be Used :				
	1. K.K brand 2. Sanitary fittings : Jaquar / Hinware 3. Sun mica : Marino / Santuri 4. Steel : TATA / Tisco 5. Asian Paints India Ltd only 6.				
1	Providing and fixing pre casted RCC man hole cover with frame 910x760 mm (K.K. brand only) over existing man hole including removing existing damaged cover and frame with cement mortar 1:4 as per direction	5	each	Rs.	Rs.
2	Providing and fixing pre casted RCC perforated storm water drain chambers cover with frame 670x520 mm internal diamension (K.K.brand only) existing damaged chambers with cement mortar 1:4 as per direction	5	each	Rs.	Rs.
3	Providing and fixing c.p. brass jet spray with lid / brackets of approved quality as per direction of Engineer in charge	10	each	Rs.	Rs.
4	Providing and fixing c.p.brass hand shower for EWC with lid / brackets of approved quality as per direction of Engineer in charge	10	each	Rs.	Rs.
5	Repairs the existing L G floor by adhesive , nails , screws preperly as per direction Engineer in charge etc complete	15	sq m	Rs.	Rs.
6	Repairs the existing audotorium chairs by welding , screwing , nailing etc as per direction of Engineer in charge etc complete	10	each	Rs.	Rs.
7	Labour charge for cleaning existing toilets, floors , wall tiles etc by Harpick or washing cleaning liquid / powder etc as per direction of Engineer in charge	300	sq m	Rs.	Rs.
8	Labour charges for repairing wooden Podium / Desk for (speach) including removing damaged sun mica , wooden members etc as per direction of Engineer in charge.	1	Job	Rs.	Rs.

9	Providing and fixing Gipsom wall ecostic board / wall lining as per site sample and design with professional labourers etc complete and matching with the same as per direction of Engineer in charge	15	sq m	Rs.	Rs.
10	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	4	sq m	Rs.	Rs.
11	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers	20	sq m	Rs.	Rs.
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars	100	kg	Rs.	Rs.
13	15 mm cement plaster 1 : 3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall.	10	sq m	Rs.	Rs.
14	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	10	each	Rs.	Rs.
15	Providing and fixing unplastiscised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour. 15 mm nominal bore with 45 cm length	10	sq m	Rs.	Rs.
16	Providing and fixing toilet paper holder : C.P. brass	10	sq m	Rs.	Rs.
17	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete : White solid plastic seat with lid	4	each	Rs.	Rs.
18	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device				

	(handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
	W.C. pan with ISI marked white solid plastic seat and lid	4	each	Rs.	Rs.
19	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	60	sq m	Rs.	Rs.
20	Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	50	sq m	Rs.	Rs.
21	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer sqm 35.85	50	sq m	Rs.	Rs.
22	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	50	sq m	Rs.	Rs.
23	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	2	cu m	Rs.	Rs.
				Total	Rs.

Conditions :-

1. The work is to be completed with 10 days
2. 1.50% water charges will be deducted
3. CPWD Specifications will be followed
4. Rates should be quoted in words and figure essentially

Executive Engineer

Copy to :

1. The Director computer center with a request to display the inviting quotation on the University of Delhi website.
2. Mrs. Kavita, JACT, for information and to ensure the display of the quotation on University website.
3. Section Officer-II
4. Notice Board

Executive Engineer