

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007

Ref. No. UE/

40

/DU/EM- 54 (2015-2016)

dated

25/2/15

NOTICE INVITING QUOTATIONS

Sealed item rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Electric work to be carried out in C-33 (29-31) Probyn Road, University of Delhi. 'So as to reach the office of the undersigned upto 3.00 P.M. on 27.08.2015

Sl. No.	Item	Qty	Unit	Rate	Amount
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. Group B	10	Nos.		Rs.
2	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel /PVC conduit including dismantling as required. Group B	15	Nos.		Rs.
3	Supplying and fixing following way prewired SP&N MCB distribution board of steel sheet for 240 volts on surface/ recess complete with loose wire box, terminal connectors for all incoming and outgoing circuits, duly prewired with suitable size FRLS PVC insulated copper conductor up to terminal blocks, tinned copper bus bar, neutral link, earth bar, din bar, detachable gland plate, interconnections, powder painted including earthing etc. as required. (But without MCB/ RCCB/ Isolator) 2 + 12 way, Double door	2	Nos.		Rs.
4	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	20	Nos.		Rs.
5	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 amps	2	each		Rs.
6	S/F 6 module power box with screw less decorative plate modular having 2 Nos. switch 15/16 amps and 2 Nos. socket 6 pin 15/16 amps making connection etc. as reqd.	2	each		Rs.
7	S/F tinny trip AC box complete with all accessories with plug and top on surface/recessed and making good the same etc. as reqd. at site. and 1 Nos. 25 amps G series SP MCB connection etc. as reqd. at site.	4	Nos.		Rs.
8	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	6	Nos.		Rs.
9	S/F 3 module power box with screw less decorative plate modular having 1 Nos. switch 15/16 amps and 1 Nos. socket 6 pin 15/16 amps making connection etc. as reqd.	4	Nos.		Rs.
10	S/F Fancy lights/ wall bracket with glass globe suitable for 60/100 watts GLS lamp i/c connection etc. as reqd. at site	10	Nos.		Rs.
11	S/F 8 module power box with screw less decorative plate modular having 3 Nos. switch 15/16 amps and 3 Nos. socket 6 pin 15/16 amps and indication making connection etc. as reqd.	2	Nos.		Rs.
12	S/F/1 testing and commissioning of pre wired fluroscnt fitting single box type fitting(1x40W) complete with all accessories and tube etc. as reqd. ceiling or wall i/c connection with 1.5sqmm FR PVC cond. Cable etc. as reqd. (TMC 501/136LPP) (Philips make)	4	each		Rs.
13	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel / PVC conduit as required.				
a)	1 x 1.5 sq. mm	150	mtr		Rs.
b)	2 x 2.5 sq. mm	50	mtr		Rs.
c)	2 x 4 sq. mm	125	mtr		Rs.
d)	2x10 sq.mm	20	mtr		Rs.
14	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required.				
a)	3 Modules	2	Nos.		Rs.
b)	6 Modules	2	Nos.		Rs.
c)	8 Modules	2	Nos.		Rs.
d)	12 Modules	2	Nos.		Rs.

15	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.			
a)	5/6 amps switch	20	Nos.	Rs.
b)	5/6 amps socket	8	Nos.	Rs.
16	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.			
a)	20 mm dia.	20	mtr	Rs.
b)	25mm dia.	25	mtr	Rs.
			Total	Rs.

Specific make:

Wire : Finolex/ Skytone/ RR Kabel

SP MCCB/ Isolator : Legrand/ Hagger

Switch, socket/sheet

/ Boxes/ Fan Regulator : North-West

Light Fitting : Philips

DLP Trunking : Legrand

Condition

- 1 The work should be completed in 7 days
- 2 Rates should be quoted both in words & figures.
- 3 CPWD specification in force will be followed.
- 4 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

Executive Engineer

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- 1 The Director, Computer Center with a request to display the Notice Inviting Tender on the Delhi University Website.
- 2 Sh. S.M. Goel, J.E. (E)
- 3 Mrs. Kavita, JACT to ensure the display of the tender notice on University website.
- 4 Notice Board

Executive Engineer