

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007

Ref. No. UE/

350

/DU/M- 57 (2015-2016)

dated

3/12/15

NOTICE RE-INVITING QUOTATIONS

Sealed percentage rate quotation are hereby re-invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Repair and finishing work in flat D-112 and D-105 at Reids Line Colony, University of Delhi So as to reach the office of the undersigned upto 3.00 P.M. on 03/12/15


Sl. No.	Item	Qty	Unit	Rate	Amount
1	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	5	sqm	145.40	727.00
2	Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	350	sqm	45.25	15838.00
3	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm	0.5	sqm	651.40	326.00
4	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	330	sqm	9.00	2970.00
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	130	sqm	41.35	5376.00
6	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer in- charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.	45	sqm	148.65	6689.00
7	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	5	sqm	88.50	443.00
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	0.75	cum	3672.80	2755.00
9	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	5	sqm	1071.70	5359.00
10	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	0.75	cum	497.15	373.00
11	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	5	sqm	18.15	91.00
12	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : 100 mm inlet and 75 mm outlet Sand Cast Iron S&S as per IS- 1729	3	each	686.00	2058.00

	Providing lead caulked joints to sand cast iron/centrifugally cast (spun) iron pipes and fittings of diameter : 75 mm	3	each	196.20	589.00
14	/F aluminium pipe/ curtain rods with brackets / side funnels of size upto 32 mm dia pipe (heavy type) with necessary screws etc all complete.	12	mtr	362.00	4344.00
15	Repair ceiling plaster RCC surface i/c removing the loose concrete and applying water proofing treatment with Dr. Fixit compound the rough surface the ceiling plaster bottom layer 1:3 (1cement: 3 C. sand) and top layer 1:3 (1cement: 3 fine sand) total thickness at the plaster 15 to 25 mm	16	sqm	431.00	6896.00

Total 54834.00

Condition:

- 1 The work should be completed in 20 days.
- 2 1.5 % water charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 The contractor must visit the site before quoting his rates.
- 5 CPWD specification in force will be followed.
- 6 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.


Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.54834/-


Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- 1 The Director, Computer Center with a request to display the Notice Inviting quotation the Delhi University Website.
- 2 Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 3 Notice Board


Executive Engineer

Agency

Address

Contract No.

Note:- Contractor shall enclosed the copy of labour license, Registration with EPFO, ESIC & BOW Welfare Board Otherwise their quotations will not accepted.

- b) SC/ST contractor shall enclosed copies of attested caste certificate otherwise their quotation will not be accepted.