

**ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007**

Ref. No. UE/

59

/DU/EM- 01 (2015-2016)

dated

9/12/15

NOTICE INVITING QUOTATIONS

Sealed item rate quotations are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University or the work " **Servicing /painting of existing panels and other allied electrical work in Arts Faculty Extension Building , University of Delhi** So as to reach the office of the undersigned upto 3.00 P.M. on 11/12/15

Sl. No.	Item	Unit	Qty	Rate	Amount
1	S/F bakelite sheet of following sizes i/c cutting the holes for existing switch & socket etc. as reqd.				
a)	9"x13" of 3mm thick	Nos.	3		Rs.
b)	T Cover	Nos.	50		Rs.
2	S/F 6 module power box with screw less decorative plate modular having 2 Nos. switches 15A/16A and 2 Nos. socket 6 pin 15A/16A i/c making connection etc. as reqd.	Nos.	7		Rs.
3	Providing and fixing of fan road of 3' feet i/c wiring with 2x1.5sqmm copper wire	Nos.	3		Rs.
4	S/F tinny trip AC box complete with all accessories with plug and top having 1 NOs. 25 amps G-series SP MCB on surface or recess i/c making connection etc. as reqd.	Nos.	6		Rs.
5	S/Drawing the following size FRLS of PVC insulated copper conductor cable on the existing surface/recess PVC conduit as reqd.				
a)	1x1.5sqmm	mtr	130		Rs.
b)	2x4sqmm	mtr	30		Rs.
c)	4x16 sqmm	mtr	85		Rs.
6	Supplying and fixing following modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as reqd.				
a)	5 amps switch	Nos.	8		Rs.
b)	3 pin 5/6 amps socket outlet	Nos.	3		Rs.
c)	15/16amps socket	Nos.	2		Rs.
d)	15/16amps switch	Nos.	2		Rs.
7	S/F/I testing and commissioning of pre wired flurosent fitting single box type fitting(1x40W) complete with all accessories and tube etc. as reqd. ceiling or wall i/c connection with 1.5sqmm FR PVC cond. Cable etc. as reqd. (TMC 501/136LPP) (Philips make)	Nos.	14		Rs.
8	S/F/I testing & commissioning of prewired flurosent fitting double box type fitting (2x36Watts) complete with all accessories and p/f 2 nOs. 36W tube etc. on the existing down rod i/c connection with 1.5sqmm FR PVC copper cond. Cable etc. as reqd. (TMC 501, 2X TLD 36W EBE) (Philips make)	Nos.	3		Rs.
9	Dismantling the existing wires/ switches/ socket/ exhaust fan/fitting /D.B.s conduit and all dismantling materials depositing in Engineering Store.	Job	1		Rs.
10	Supplying and fixing following sizes /modules, G.I. box along with modular base & cover plate for modular switches in recess etc. as reqd.				
a)	8 Module (125mm x 125mm)	Nos.	2		Rs.
b)	12 Module (200mm x 150mm)	Nos.	1		Rs.
11	Supplying & fixing of following sizes of medium class PVC conduit/ batten along with all accessories in surface/recessed including cutting the wall and making good the same in case of recessed conduit as reqd.				
a)	25mm	mtr	250		Rs.
12	Supplying and fixing 2 Module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as reqd.	Nos.	5		Rs.
13	Making provision for dressing the existing hanging wires of all types and cables providing work suitable arrangement etc. as reqd.	Job	1		Rs.

Description	Nos.	Rs.
Servicing the LT cubical panel with blower and painting the same with two or more coats as required i/c testing all the nut bolts and connecting and tightening the same as reqd.	7	Rs.
S/F 10 watts LED ceiling circular fitting complete with all accessories i/c making connection etc. as reqd.	3	Rs.
S/F flexible pipe of 32mm i/c shutting the same as reqd.	mtr 50	Rs.
S/F thimble of 16sqmm i/c crimping and taping etc. as reqd. and making connection	Nos. 432	Rs.
S/F 100amps MCCB of 10 KA 3 pole in the existing DB i/c making connection etc. as reqd.	Nos. 1	Rs.
Servicing/ cleaning of the existing MCB DB with air blower, testing/balancing the load of DB, dressing up the wires, thimbling and tightening of screws of all the MCB DB and connection etc. as reqd.	Nos. 20	Rs.
Total		Rs.

Specific make:-

- Wire:- Skytone/Havells/ Finolex/ RR Kabel
- SP MCB/ DP/FP:- Hagger/ Seimens/ABB/L&T/ Legrand
- Switch/Socket:- North-West/ Legrand/Seimens
- Light Fitting :- Philips
- PVC Conduit/ Batten:- AKG/BEC
- DLP Trunking :- Legrand
- LED Street Light:- Polycab/HPL/Stark

Condition:

- 1 The work should be completed in 20 days.
- 2 Rates should be quoted both in words & figures.
- 3 CPWD specification in force will be followed.
- 4 Contractor shall enclose copies of EPFO and ESIC
- 5 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

[Signature]
Executive Engineer

Undertaking:
I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.
(Contractor)

Copy to:-

- 1 The Director, Computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- 3 Sh. Devendra Kumar, J.E. (E)
- ✓ Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 5 Notice Board

[Signature]
Executive Engineer