

**ENGINEERING DEPARTMENT  
UNIVERSITY OF DELHI  
DELHI-110007**

Ref. No. UE/ 64

/DU/EM- 01 (2015-2016)

dated 31-12-15

**NOTICE INVITING QUOTATIONS**

Sealed item rate quotations are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work " **Electrical repairing work and provision of power points in room no. 3, 4, 27, 28, 29, 32 and 33 of Faculty of Management Studies, University of Delhi** "So as to reach the office of the undersigned upto 3.00 P.M. on 05/01/2016

Sl. No.	Item	Unit	Qty	Rate	Amount
1	S/F DLP UPVC trunking of 80 mmx 50mm compartment with cover clip on separates partition left right top internal angle, flat angle raise function flat function cover to body joints mosaic clip & support from mosaic isolation bracket 2mm thick plastic.	mtr	24		Rs.
2	S/F/I testing and commissioning of pre wired fluroscent fitting single box type fitting(1x40W) complete with all accessories and tube etc. as reqd. ceiling or wall i/c connection with 1.5sqmmm FR PVC cond. Cable etc. as reqd. (TMC 501/136LPP) (Philips make)	Nos.	10		Rs.
3	S/F/I testing & commissioning of prewired fluorescent fitting double box type fitting (2x36Watts) complete with all accessories and p/f 2 nOs. 36W tube etc. on the existing down rod i/c connection with 1.5sqmm FR PVC copper cond. Cable etc. as reqd. (TMC 501, 2X TLD 36W EBE) (Philips make)	Nos.	20		Rs.
4	S/F 6 module power box with screw less decorative plate modular having 2 Nos. switches 15A/16A and 2 Nos. socket 6 pin 15A/16A i/c making connection etc. as reqd.	Nos.	15		Rs.
5	Dismantling the existing wires/ switches/ socket/ starter/ fitting/ D.B.s / conduit and all dismantling materials depositing in Engineering Store	Job	1		Rs.
6	S/F tiny trip AC box complete with all accessories with plug and top having 1 NOs. 25 amps G-series SP MCB on surface or recess i/c making connection etc. as reqd.	Nos.	6		Rs.
7	P/F ceiling circular LED fitting 10 watts for surface mounting.	Nos.	4		Rs.
8	S/I/T/C of LED AC street light fitting of 40watts (IP-66> 3000 Lumens) complete with all accessories etc. as reqd. at site.	Nos.	1		Rs.
9	Supplying and fixing of following size/ modules, G.I box along with modular base & cover plate for modular switches in recess etc. as reqd.				
a)	12 Module (200mm x 150mm)	Nos.	5		Rs.
b)	8 Module (125mm x 125mm)	Nos.	2		Rs.
10	S/D the following size FRLS of PVC insulated copper conductor cable in the existing surface/recess PVC conduit etc. as reqd.				
a)	1x1.5sqmm	mtr	450		Rs.
b)	2x2.5sqmm	mtr	100		Rs.
c)	2x4sqmm	mtr	200		Rs.
d)	2x6sqmm	mtr	150		Rs.
11	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as reqd.				
a)	5/6 amps switch	Nos.	80		Rs.
b)	3 pin 5/6 amps socket outlet	Nos.	8		Rs.
12	Supplying and fixing 3 pin, 5 amps ceiling rose on the existiing junction box/ wooden block including connection etc. as required.	Nos.	15		Rs.
13	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. Group C	Nos.	10		Rs.

14	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel PVC conduit including dismantling as required. Group C	Nos.	70	Rs.
15	Supplying and fixing suitable sizes G.I. box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as reqd.	Nos.	6	Rs.
16	Supplying & fixing of following sizes of medium class PVC conduit/ batten along with all accessories in surface/recessed including cutting the wall and making good the same in case of recessed conduit as reqd.			
a)	25mm	mtr	75	Rs.
b)	32mm	mtr	50	Rs.
17	Supplying and fixing 2 Module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as reqd.	Nos.	12	Rs.

**Total**      Rs.

**Specific make:-**

- Wire:- Skytone/Havells/ Finolex/ RR Kabel
- SP MCB/ DP/FP:- Hagger/ Seimens/ABB/L&T/ Legrand
- Switch/Socket:- North-West/ Legrand/Seimens
- Light Fitting :- Philips
- PVC Conduit/ Batten:- AKG/BEC
- DLP Trunking:- Legrand
- LED Street Light:- Polycab/HPL/Stark

**Condition:**

- 1 The work should be completed in 30 days.
- 2 Rates should be quoted both in words & figures.
- 3 CPWD specification in force will be followed.
- 4 Contractor shall enclose copies of EPFO and ESIC
- 5 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

  
Executive Engineer


**Undertaking:**

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

**Copy to:-**

- 1 The Director, Computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- 2 Sh. Devendra Kumar, J.E. (E)
- 3 Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 4 Notice Board

  
Executive Engineer