

**ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007**

Ref. No. UE/

399

/DU/M- 57 (2015-2016)

dated

11/1/16

NOTICE INVITING QUOTATIONS

Sealed item rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Repair/ misc. work in flat D-6 Reids Line Colony, University of Delhi So as to reach the office of the undersigned upto 3.00 P.M. on.....15-1-2016

Sl. No.	Item	Qty	Unit	Rate	Amount
1	Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	160	sqm	Rs.	
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	70	sqm	Rs.	
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	160	sqm	Rs.	
4	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab over 0.50 sqm	2	sqm	Rs.	
5	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : 35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood	4	sqm	Rs.	
6	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	0.03	cum	Rs.	
7	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : 100 mm	4	each	Rs.	
8	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete :			Rs.	
a)	150x10 mm	4	Nos.	Rs.	
b)	100x10 mm	4	Nos.	Rs.	
9	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre capacity - White	1	each	Rs.	
10	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	100	sqm	Rs.	
11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	3	cum	Rs.	
12	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	30	sqm	Rs.	

14	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing	3	sqm	Rs.
	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.			
a)	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	1.5	cum	Rs.
b)	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	3	cum	Rs.
15	Disposal of building rubbish/ malba/ similar unserviceable, dismantled or waste materials by mechanical means, including loading transporting, unloading to approved municipal dumping ground or as approved by Engineer-in Charge i/c carriage upto 12km	3	cum	Rs.
16	P/F aluminium pipe/ curtain rods with brackets / side funnels of size upto 32 mm dia pipe (heavy type) with necessary screws etc all complete.	12	mtr	Rs.
17	Providing and applying birla / JK wall putty on wall surface (one or more coats) as required in thickness 1 mm i/c sand papering etc to prepare smooth as per direction of Engineer-in-charge.	100	sqm	Rs.
18	Repair of door i/c taking out, repair, refixing and locking arrangement etc complete	4	Nos.	Rs.

Total **Rs.**

Condition:

- 1 The work should be completed in 30 days.
- 2 1.5 % water charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 The contractor must visit the site before quoting his rates.
- 5 CPWD specification in force will be followed.
- 6 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

Sr
Executive Engineer

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- 1 The Director, Computer Center with a request to display the Notice Inviting quotation the Delhi University Website.
- ✓ 2 Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 3 Notice Board

Kr 9/11
Executive Engineer

Agency

Address

Contract No.

- Note:- a Contractor shall enclosed the copy of labour license, Registration with EPFO, ESIC & ROW Welfare Board Otherwise their quotations will not accepted.
- b) SC/ST contractor shall enclosed copies of attested caste certificate otherwise their quotation will not be accepted.