

**ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007**

Ref. No. UE/

400

/DU/M- 57 (2015-2016)

dated

11/1/16

NOTICE INVITING QUOTATIONS

Sealed item rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Repair of chajjas C-129 to C-132 and misc. finishing work in C-129 at Reids Line Colony, University of Delhi" So as to reach the office of the undersigned upto 3.00 P.M. on 15-1-2016

Sl. No.	Item	Qty	Unit	Rate	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	3	cum		Rs.
2	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	0.75	cum		Rs.
3	Centering and shuttering including strutting, propping etc. and removal of form for : Shelves (Cast in situ)	7	sqm		Rs.
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Cold twisted bars	75	kg		Rs.
5	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	30	sqm		Rs.
6	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	3	sqm		Rs.
7	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	10	sqm		Rs.
8	Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	160	sqm		Rs.
9	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	160	sqm		Rs.
10	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm	0.5	sqm		Rs.
11	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	160	sqm		Rs.
12	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge .The elevational area of the scaffolding shall be measured for payment purpose	100	sqm		Rs.
13	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
a)	Nominal concrete 1:3:6 or richer mix (1/c equivalent design mix)	1	cum		Rs.
b)	Nominal concrete 1:4:8 or leaner mix (1/c equivalent design mix)	3	cum		Rs.
14	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	0.6	cum		Rs.
15	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	5	sqm		Rs.
16	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead : Of area 3 sq. metres and below	2	each		Rs.

	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. Second class teak wood 35 mm thick shutters	4	sqm	Rs.
18	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick : Second class teak wood	2.5	sqm	Rs.
19	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete. With 12 mm mild steel U beading	3.5	sqm	Rs.
20	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 300x16 mm	2	each	Rs.
21	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : 150x10 mm	6	each	Rs.
22	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : 125 mm	2	each	Rs.
23	Applying priming coat : With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	10	sqm	Rs.
24	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	10	sqm	Rs.
25	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	70	sqm	Rs.
26	P/F aluminium pipe/ curtain rods with brackets / side funnels of size upto 32 mm dia pipe (heavy type) with necessary screws etc all complete.	12	mtr	Rs.
27	Providing and applying birla / JK wall putty on wall surface (one or more coats) as required in thickness 1 mm i/c sand papering etc to prepare smooth as per direction of Engineer-in-charge.	100	sqm	Rs.
28	Disposal of building rubbish/ malba/ similar unserviceable, dismantled or waste materials by mechanical means, including loading transporting, unloading to approved municipal dumping ground or as approved by Engineer-in Charge i/c carriage upto 12km	5	cum	Rs.
Total				Rs.

Condition:

- 1 The work should be completed in 45 days.
- 2 2% water/electricity charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 The contractor must visit the site before quoting his rates.
- 5 CPWD specification in force will be followed.
- 6 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

- Jcd -
Executive Engineer

Undertaking:
I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.
(Contractor)

Copy to:-

- 1 The Director, Computer Center with a request to display the Notice Inviting quotation the Delhi University Website.
- 2 Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 3 Notice Board

Executive Engineer

Agency

Address

Contract No.

- Note:-a Contractor shall enclosed the copy of labour license, Registration with EPFO, ESIC & BOW Welfare Board Otherwise their quotations will not accepted.
- b) SC/ST contractor shall enclosed copies of attested caste certificate otherwise their quotation will not be accepted.

se