

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007

NOTICE INVITING QUOTATIONS
(2015-2016)

dated 13.1.16

Ref. No. UE/402

/DU/M- 54

Sealed item rate quotations are hereby invited from the contractors enlisted with CPWD, MES, Railways and any Govt./ public sector undertaking and working contractor of Delhi University for the work " Urgent misc. item of work in C-5 (29-31) Probyn Road, University of Delhi " "So as to reach the office of the undersigned upto 3.00 P.M. on 18-1-16

S. No	Description of Items	Unit	Qty	Rate	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	3		
2	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	0.2		
3	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers	sqm	2		
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Cold twisted bars	kg	60		
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg	200		
6	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	12		
7	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty Float glass panes of thickness 4 mm	sqm	1		
8	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	sqm	300		
9	Brick edging laid lengthwise with half brick depth including excavation, refilling and disposal of surplus earth lead upto 50 metres : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	mtr	20		
10	Providing and fixing controlled flush, low level cistern made of vitreous china with all fittings complete. 10 litre (full flush) capacity-white	each	2		
11	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 15 mm dia nominal bore	mtr	30		
12	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	each	2		
13	Providing and fixing brass stop cock of approved quality : 15 mm nominal bore	each	2		
14	Painting G.I. pipes and fittings with synthetic enamel white paint with two coats over a ready mixed priming coat, both of approved quality for new work : 15 mm diameter pipe	mtr	30		
15	Providing and fixing G.I. Union in G.I. pipe Including cutting and threading the pipe and making long screws etc. complete (New work) : 15 mm nominal bore	each	4		
16	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, ISI : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	ltr	1000		

- | | | | |
|----|--|------|---|
| 17 | Supplying and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design: 100x100 mm size P type With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 | each | 1 |
| 18 | Supplying and fixing C.I. cover without frame for manholes :455 x 610 mm rectangular C.I. cover (light duty) the weight of the cover to be not less than 23 kg | each | 1 |
| 19 | Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved | cum | 6 |

Total Rs.

Condition:

- 1 The work should be completed in 20 days.
- 2 1.50 % water/ electric charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore
- 5 SC/ ST contractors should enclose copies of attested caste certificate otherwise their quotation will not be accepted.
- 6 Contractor should enclose the copy of Labour Licence, Registration with EPFO, ESIC & BOCW Welfare Board otherwise their quotation will not be accepted



Executive Engineer

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

Contractor

- 1 The Director, Computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- 2 Sh. Jacob John J.E. (C)
- 3 Ms. Kavita, J.A.C.T. to ensure the display of the tender notice on University website
- 4 Notice Board.



Executive Engineer