

Office of the Executive Engineer

SC-

January 21, 2016

Sealed percentage rate quotations are here by invited from the contractors enlisted with CPWD, MES, Railways and working contractors of Delhi University for the work of “**Repair and painting work in flat no. 4, type-II, block-I housing unit at South Campus, University of Delhi.**” so as to reach the office of undersigned on dated **29.01.2016** by 3.00P.M. the quotations will be opened on the same day at 3:30P.M.

SLNo	Description	Qty	Unit	Rate	Amount
1	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :				
	25 mm thick	2.5	sqm	1071.70	2679.00
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :				
	New work (two or more coats) over and including water thinnable priming coat with cement primer	160	sqm	79.65	12744.00
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	Two or more coats on new work	80	sqm	63.05	5044.00
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.				
		90	sqm	85.40	7686.00
5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.				
		160	sqm	9.00	1440.00
6	Repoar of door/window/racks etc. steel or wood as per the requirement with necessary fittings etc. complete.				
		2	each	350.00	700.00
7	Disposal malba at side the Campus.	0.5	mtr	300.00	150.00

8	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	2.5	sqm	88.50	221.00
Total					30664.00

Conditions

1. The work is to be carried out as per CPWD specifications.
2. The time allowed to complete the work 10 days.
3. 1% water charges to be deducted from the bill.
4. The rate quoted should be inclusive of all taxes and duties & should be written both in words and figures.
5. The contractor should see the site before quoting the rate.
6. Undersigned reserves the right to reject any or all the quotations without assigning any reason thereof.
7. The contractors are required to submit a copy of Labour Licence Registration with EPFO, ESIC and BOCW Welfare Board.

Executive Engineer
South Campus

I/we _____ hereby agree to execute the above
@ _____ % Above/Below/At Par the estimated cost.

Signature _____

Name _____

Address _____

Telephone _____