

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI

Ref no. UE/ ⁴⁰⁵ / DU/ M- 92 (2015-16) dated 25/1/16

Sealed item rate quotations are hereby re-invited from Contractors enlisted with CPWD, MES, Railways and other Contractors of Delhi University for the work "Repairs the damaged Asbestos roof over existing Garage and other misc work in Kitchen in R T residence at VKRV Rao Hostel, University of Delhi. So as to reach the office of the undersigned at 3.00 P.M on dated 29.01.2016

S.No	Description of item	Qty	Unit	Rate	Amount
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of : Asbestos sheet	15	sq m	Rs.	Rs.
2	Providing and fixing hard drawn steel wire fabric 75x25 mm mesh of weight not less than 7.75 Kg per sqm to window frames / etc. including 20 x 5 mm m.s. beading of and priming coat with approved steel primer all complete	5	sq m	Rs.	Rs.
3	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete. With 12 mm mild steel 20x5 mm beading sqm 578.30	6	sq m	Rs.	Rs.
4	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	16	sq m	Rs.	Rs.
5	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	0.25	cu m	Rs.	Rs.
6	Centering and shuttering including strutting, propping etc. and removal of form for : Shelves (Cast in situ)	4	sq m	Rs.	Rs.
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars	10	kg	Rs.	Rs.

8	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 25 mm thick (for cupboard) including ISI marked nickel plated bright finished M.S. piano hinges with necessary screws	4	sq m	Rs.	Rs.
9	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : 75 mm	4	each	Rs.	Rs.
10	Providing and fixing oxidised M.S. hasp and staple (safety type) conforming to IS : 363 with necessary screws etc. complete : 150 mm	2	each	Rs.	Rs.
11	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : 150x10 mm	4	each	Rs.	Rs.
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	50	sq m	Rs.	Rs.
			Total	Rs.	

Conditions :-

1. The work is to be completed with 15 days
2. 1.50% water charges will be deducted
3. CPWD Specifications will be followed
4. Rates should be quoted both in words & figures.
5. Undersigned reserves the authority to reject any or all the quotation without any reason therefore .
6. SC/ST Contractors shall enclosed copies of attested cast certificate other wise there quotation will be acci
7. Contractor shall enclosed the copy of Labour Licence Registration with ETFO , ESIC and BOCW welfare box other wise there quotation will not be accepted .

Executive Engineer

Copy to :

1. The Director computer center with a request to display the inviting quotation on the University of Delhi website.
2. Mrs. Kavita , JACT , for information and to ensure the display of the quotation on University website.
3. Section Officer -II
4. Notice Board

Kesh
21.1.16
Executive Engineer