

ENGINEERING DEPARTMENT

UNIVERSITY OF DELHI

Delhi 110007

NOTICE INVITING QUOTATION

Ref. No. UE/ 309 /DU/M-11 (2020-2021)

6/10/21

dated

Sealed percentage rate quotation are hereby invited from the contractors enlisted with CPWD., MES, Railways and any Govt./public sector undertaking and working contractor of Delhi University for the work "Repair of hanging water supply line at IInd floor toilet Gawyer Hall Hostel, University of Delhi." So as to reach the office of the undersigned up to 3.00 PM on 13/10/21

1.	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 25 mm dia nominal bore	metre	8	438.00	3504.00
2.	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	each	1	673.45	673.45
3.	Painting G.I. pipes and fittings with synthetic enamel white paint with two coats over a ready mixed priming coat, both of approved quality for new work : 25 mm diameter pipe	metre	8	23.70	189.60
4.	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc complete (New work) : 25 mm dia nominal bore	each	1	340.10	340.10
5.	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube chalis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/or pointing and/or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per direction and approval of Engineer-in-charge.	sqm	40	257.95	10318.00
6.	Repair the damaged G.I. line with required G.I. pipe and fittings etc complete as per direction of Engineer-in-charge (1" to 25 mm)	each	1	3676.63	3676.63
7.	Removal blockage like road gully chamber, sewer manhole, GT and SCI pipe line etc complete as per direction of Engineer-in-charge.	each	4	957.29	3829.16
				Total	22530.94

Condition:-

1. The work should be completed in 07 days.
2. 1.50% water/Electric charges will be deducted.
3. Rates should be quoted both in words & figures.
4. The contractor must visit the site before quoting the rates.
5. CPWD specification in force will be followed.
6. Undersigned reserves the authority to reject any or all the quotation without assigning.

Executive Engineer

I/we hereby quote.....% above/ below/ at par on the estimated cost of Rs. 22530.94

Undertaking I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

1. The Director, Computer Center with a request to display the Notice inviting quotation on the Delhi University Website.
2. Sh. Adil Mahmood, J.E.(C)
3. Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
4. Notice Board

Executive Engineer