

ENGINEERING DEPARTMENT

UNIVERSITY OF DELHI

DELHI-110007

Ref. No. CE/

597

/DU/M- (2021-2022)

dated

7/1/2022

NOTICE INVITING QUOTATION

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work " Repairing/ laying red stone /Delhi Stone back side gate at V.C. Office, University of Delhi." So as to reach the office of the undersigned upto 3.00 P.M. on.....14/1/2022

Sl. No.	Item	Qty	Unit	Rate	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	cum	1.5	6788.6	10182.90
2	Providing sand stone slab for roofing and laying them in cement mortar 1 : 4 (1 cement : 4 coarse sand) over wooden karries or R.C.C. battens or structural steel sections (Karries or battens or structural steel sections to be paid separately), including pointing the ceiling joints with cement mortar 1:3 (1 cement : 3 fine sand) complete : Red sand stone slab 40 to 50 mm thick	sqm	2	793.1	1586.20
3	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of all dirt, scales, oil, grease and other foreign material etc. and lining out complete. New work (Two or more coats)	sqm	10	150.85	1508.50
4	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge)	cum	1	8376.15	8376.15
5	Labour charges for taking and refixing Delhi Stone with cement mortar 1:3 (1 cement:3 Coarse sand) and pointing etc complete as per direction of Engineer-in-charge.	sqm	6	533	3198.00
				Total	24851.75
				Say	24852

Condition:

- The work should be completed in 07 days.
- 1.5% water charges will be deducted.
- Rates should be quoted both in words & figures.
- The contractor must visit the site before quoting his rates.
- CPWD specification in force will be followed.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.24852.00

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.
(Contractor)

Copy to:-

- The Director, Computer Center with a request to display the Notice Inviting quotation on the Delhi University Website.
- Sh. V.K. Meena, J.E. (C)
- ✓ Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- Notice Board

Executive Engineer