

ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007

Ref. No. CE/

512

/DU/M- (2021-2022)

dated

14/12/21

NOTICE INVITING QUOTATION

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Fixing of broken / false ceiling on 2nd floor DSE Main Building, University of Delhi." So as to reach the office of the undersigned upto 3.00 P.M. on..... 21/12/21

Sl. No.	Item	Qty	Unit	Rate	Amount
1	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. 12.52.1 GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	sqm	5	1504.45	7522.25
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	sqm	90	153.45	13810.50
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work	sqm	10	121.55	1215.50
4	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	90	18.25	1642.50
5	Repairing of floor trap with grouting etc complete in all respect.	each	2	363	726.00
				Total	24916.75
				Say	24917

Condition:

- 1 The work should be completed in 07 days.
- 2 1.50% water charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 The contractor must visit the site before quoting his rates.
- 5 CPWD specification in force will be followed.
- 7 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.24,917.00

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.
(Contractor)

Copy to:-

- 1 The Director, Computer Center with a request to display the Notice Inviting quotation on the Delhi University Website.
- 2 Sh. V.K. Meena, J.E. (C)
- 3 Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 4 Notice Board

Executive Engineer

14/12/21